




The Current Status of ALMA (slideshow version)

Alison Peck
Deputy Project Scientist
Joint ALMA Observatory, Santiago



What do we want?



CASA beam and u,v coverage simulations soon to be online for proposal planning

- High Fidelity Imaging
- Precise Imaging at 0.1" Resolution
- Routine Sub-mJy Continuum Sensitivity
- Routine mK Spectral Sensitivity
- Wideband Frequency Coverage
- Wide Field Imaging Mosaicing
- Submillimeter Receiver System
- Full Polarization Capability
- System Flexibility



How do we get it?

Technical Specifications

- 54 12-m antennas, 12 7-m antennas, at 5000m site
- Surface accuracy $\pm 25 \mu\text{m}$, 0.6" reference pointing in 9m/s wind, 2" absolute pointing all-sky.
- Array configurations between 150m to ~15-18km.
- 10 bands in 31-950 GHz + 183 GHz WVR.
- 8 GHz BW, dual polarization.
- Interferometry, mosaicing & total-power observing.
- Correlator: 4096 channels/IF (multi-IF), full Stokes.
- Data rate: 6Mb/s average; peak 64 Mb/s.
- All data archived (raw + images), pipeline processing.

During full operations, the estimated flow of int/SD data into archive ~100 Tb per year.

Project lifecycle: online proposal tool, script generator, dynamic scheduling, raw data available plus a reference image with pipeline processing history, calibration data...



ALMA Sites

- **Array Operations Site – AOS** – 5000m – Antennas, correlator, some (oxygenated) office space
- **Operations Support Facility – OSF** – 3000m – Array operation, equipment maintenance, living quarters
- **ALMA Test Facility – ATF** – Socorro, VLA site – prototype antennas, software development
- **Santiago Central Offices – SCO** – Administration, scientific support. Will be located near ESO, currently Las Condes (also JAO - Joint ALMA Observatory)
- **ALMA Regional Centers – ARCs + ARC nodes** – interfaces to astronomy community




Approximate Schedule

- .First fringes ATF: Q2 2007
- .First fringes Chile: Q1 2009
- .AOS, OSF facilities: Complete
 - Start move in (w/ furniture and power) end 2008
- .Antennas: 11 now on site in assembly,
 - First 2 acceptance by AIV: Q4 2008
- .Front Ends: #1 delivered, install Oct 2008
 - #2 - end 2008
- .Correlator: 1st quadrant being installed at AOS
 - ACA correlator installed at AOS
 - New 2-antenna correlator installed at OSF

- .Call for Early Science: 2010
- .Early Science: 2010-11
- .Full Operations: ~2012



Receivers / Front Ends



ALMA Band	Frequency Range	Receiver noise temperature		Mixing scheme	Receiver technology
		T _{RX} over 80% of the RF band	T _{RX} at any RF frequency		
1	31.3 – 45 GHz	17 K	28 K	USB	HEMT
2	67 – 90 GHz	30 K	50 K	LSB	HEMT
3	84 – 116 GHz	37 K	62 K	2SB	SIS
4	125 – 169 GHz	51 K	85 K	2SB	SIS
5	163 - 211 GHz	65 K	108 K	2SB	SIS
6	211 – 275 GHz	83 K	138 K	2SB	SIS
7	275 – 373 GHz	147 K	221 K	2SB	SIS
8	385 – 500 GHz	98 K	147 K	DSB	SIS
9	602 – 720 GHz	175 K	263 K	DSB	SIS
10	787 – 950 GHz	230 K	345 K	DSB	SIS

Initially for CSV, Bands 3 and 6 on all antennas, plus Band 7 or 9



Operations Support Facility (OSF): Technical Facilities 3000m



ALMA Site OSF CAM 2 -- 2008-09-26--11:45:11

Contractor's Camp
holds ~440 persons



OSF Warehouse and Offices





ALMA Camp - OSF



Scientist
dorms

Bunkhouse
dorms

Medical
center

AIV Lab

Offices and
cantina

Tennis court



Inset:
Scientist dorms

Transformational

September 27, 2008



First Front End Installation at OSF lab in Chile, April 2008





First FE / Second BE being tested at OSF



Vendor camps - with dust devil





Vertex #1 - Fully assembled and being tested





Vertex #2, straight off the truck, Sept 2007
now assembled and outside being tested





Assembly of Vertex #2 and 3 - late 2007





Four Complete Mitsubishi 12m Antennas (March 2008)





Back End racks being lifted into MELCO #2 receiver cabin



AEM #1



- CFRP cabin
- Stiff yoke
- Direct drives

Drive tests complete

Stiffer Az bearing support being added





Transporter being unloaded in Chile - February 2008



On the road to the OSF

September 27, 2008



First Transporter Outing - OSF to AOS

April 2008



First Move - Vertex#2 from Hangar to outside pad for testing



First Move of ALMA Antenna
(July 8, 2008)






Chajnantor Plateau – looking north

V. Licancabur

C⁰ Chajnantor

Pampa La Bola



Center of Array



AOS Technical Building



AOS Technical Building - completed 2008




Simulation of Extended Configuration



12m Array

Simulation (!)



Atacama Compact Array (ACA)



Central Cluster



grading
underway



Foundation being kept warm while it cures





Correlator First Quadrant at AOS



Transformational Science with ALMA

September 27, 2008




Correlator first quadrant being installed






Amplitude (front view)
-15.000 to 0.000 by 3.000




Normal errors (front view)
-125.000 to 125.000 by 50.000



Preliminary Holography Results:
Done on both ME1Co and Vertex antennas -
Now Preparing for Antenna Acceptance by ALMA



Data taken using prototype optical pointing telescope on production antenna-- rms~1.4 asec





Prototype Antennas at ATF (2006)

Mitsubishi antenna (in Chile now...)

Vertex antenna



AEC antenna



12-m, Carbon Fiber Support Structure





Interferometric spectrum: Orion - 101 GHz, April 2008




Taken at ATF, not using production receivers, but verifying software for control, tuning, correlator and data reduction

(Thanks to Hunter, Indebetouw, Wootten, etc)



Transformational Science with ALMA

September 27, 2008




Most recent:
Sgr B2 Spectrum
97.9 GHz

(Thanks to de Gregorio,
Fomalont, Remijan, Biggs,
CASA and Control s/w
people)

**Raster on Moon with
Total Power detectors**

**Taken at ATF, not
using production
receivers, but
verifying software
for control, tuning,
correlator and data
reduction**





Where you come in...

Current job advertisements:

Charlottesville	CV4896	NAASC Postdoc - CASA
Charlottesville	CV4888	NAASC Postdoc - Splatalogue
Charlottesville	CV4870	ALMA FEIC Technical Leader
Charlottesville	CV4853	NAASC Scientist - CSV Liaison
Charlottesville	CV3682	Scientist - CASA Developer
Socorro, NM	SO3391	CASA Group Supervisor
Santiago, Chile	CL4845	Commissioning Scientists

Visitor's program:

- Some support (typically at least travel and lodging) for people who can take leave or sabbatical from their home institutions to participate in CSV.
- Beginning mid 2009.
- Stays of 3 months to 1 year recommended
- NO "own" data during this period
- Check alma.cl web page soon for more info, or contact me at apeck@alma.cl



For more info:

www.alma.cl

Or email apeck@alma.cl

The Atacama Large Millimeter Array (ALMA) is an international astronomy facility. ALMA is a partnership between Europe, North America and Japan, in cooperation with the Republic of Chile. ALMA is funded in North America by the U.S. National Science Foundation (NSF) in cooperation with the National Research Council of Canada (NRC), in Europe by the European Southern Observatory (ESO) and Spain. ALMA construction and operations are led on behalf of North America by the National Radio Astronomy Observatory (NRAO), which is managed by Associated Universities, Inc. (AUI), on behalf of Europe by ESO, and on behalf of Japan by the National Astronomical Observatory of Japan.



ALMA Median Sensitivity

(1 minute; 75% Quartile opacities $\lambda > 1\text{mm}$, 25% $\lambda < 1\text{mm}$)

Frequency (GHz)	Continuum (mJy)	Line 1 km s ⁻¹ (mJy)	Line 25 km s ⁻¹ (mJy)
35	0.02	5.1	1.03
110	0.027	4.4	0.89
140	0.039	5.1	1.01
230	0.071	7.2	1.44
345	0.12	10	1.99
675	0.85	51	10.2
850	1.26	66	13.3